

- | | | |
|---|-----------------------|-------|
| # | ROOF PLAN KEYED NOTES | 3 |
| | NOT TO SCALE | E-104 |

- ① DISCONNECT SWITCH PROVIDED WITH UNIT.
- ② COMBINATION 30A, 2P, 2F, WP DISCONNECT SWITCH WITH RK5 FUSES PER MANUFACTURER RECOMMENDATION.
- ③ COMBINE CIRCUITRY IN 1" CONDUIT FROM J-BOX ON EQUIPMENT DISCONNECT SWITCH SUPPORT.
REFER TO DETAIL THIS SHEET, 1/E-104.
- ④ ELECTRICAL FEEDS ARE TO BE ROUTED FROM PLENUM SPACE, UP THROUGH EQUIPMENT CURB, INTO BOTTOM OF EQUIPMENT, THROUGH FACTORY INSTALLED WATER TIGHT CONNECTIONS.

- | | |
|-------------------------|-------|
| HVAC EQUIPMENT SCHEDULE | 4 |
| NOT TO SCALE | E-104 |

